



DUVRI (Interference Risk Assessment Document)

Unified document on assessment of risks generated by interference among activities conducted simultaneously in the same workplace.

"ModenaFiere" Exhibition Centre

Ref.: Art. 26 Leg. Dec. 81/08 as amended

Art. 26 Obligations relating to tender, work, or supply contracts.

- 1. If the employer assigns works, services and supplies to a contracting firm or to self-employed workers within the company, or to a single production units of same, as well as in the context of the company's entire production cycle, the employer:
- a) must check, using the methods provided by the decree referred to in Article 6, sub-section 8, letter g), the technical and professional qualifications of said contracting firms or self-employed workers in relation to the works to be assigned by contract or by means of work or supply contract. Until the effective date of the decree referred to in the preceding sentence, this check is to be conducted as follows:
- 1) a certificate of registration must be obtained from the chamber of commerce, industry and artisanship;
- 2) the contracting firm or self-employed workers must provide self-certification that they meet the technical and professional qualification requirements pursuant to article 47 of consolidated text of the laws and regulations pertaining to administrative documentation, as referred to the Italian Presidential Decree no. 445 of 28 December 2000;
- b) these parties must be given detailed information on the specific risks that exist in the place in which they are called on to work and on the preventive and emergency measures adopted in relation to their activities.
- 2. In the situation referred to in sub-section 1, employers, including subcontractors, must:
- a) cooperate in implementing measures to prevent and protect against risks of workplace accidents relating to the work activity established in the contract;
- b) coordinate procedures to prevent and protect against risks to which workers are exposed by sharing information for purposes that include eliminating risks due to interference between work carried out by the various companies involved.
- 3. The employer must promote cooperation and coordination as indicated in sub-section 2 by preparing a unified risk assessment document that specifies the measures adopted to eliminate or, if this is not possible, reduce to a minimum, risks due to interference. This document must be attached to the supply or work contract (.......). The provisions of this sub-section are not applicable to specific risks peculiar to the activity of contracting firms or of individual self-employed workers.
- 4. Without prejudice to current legal provisions regarding joint liability for non-payment of wages and of social security and insurance contributions, the employer is jointly liable with the contractor and with each sub-contractor (if any) for all injuries for which the worker, whether employed by the contractor or by the sub-contractor, is not compensated by the National Institute for Industrial Accident Insurance (INAIL) or by the Social Security Institute for the Maritime Industry (IPSEMA). The provisions of this sub-section are not applicable to injuries deriving from specific risks peculiar to the activity of contracting or sub-contracting firms.
- 5. Costs related to work safety, in particular those peculiar to the activity of the contracting firm, must be explicitly stated in each sub-contract, contract, and supply contract, even if existing at the effective date of Article 1559 of this Decree, with the exception of contracts for the supply of essential goods and services (articles 1655, 1656 and 1677 of the Italian Civil Code), subject to invalidity in accordance with article 1418 of the Italian Civil Code. (......).
- On request, this data may be accessed by the safety representative and by local officers of major national labour unions. 6,7.(......)
- 8. All workers employed by the contractor or sub-contractor must wear a photo identification badge indicating the worker's name and the employer's name when doing any work subject to a contract or sub-contract.

Date: 14 October 2013	Rev. 02/2013
-----------------------	--------------

1. GENERAL

This document is the "UNIFIED DOCUMENT ON ASSESSMENT OF RISKS INDICATING MEASURES ADOPTED TO ELIMINATE INTERFERENCE" ("DUVRI - Interference Risk Assessment Document") as required by Article 26 of Italian Legislative Decree 81/2008 as amended.

Cooperation agreements in force between the Organiser and each Exhibitor are formalised by way of the agreement in possession of the parties.

This document is an integral part of the "Technical Regulations and Conditions for Participation in the Exhibition" and "Safety Regulations of the Exhibition Centre" attached hereto and refers to the periods of activity in the exhibition centre identified as follows:

- pre exhibition: fitting up days in preparation for an event;
- exhibition: ongoing event;
- post exhibition: dismantling days.

These periods are defined in the above mentioned "Technical Regulations and Conditions for Participation in the Exhibition".

This document is relevant to the following parties:

a) ModenaFiere srl

Company Name: ModenaFiere srl, with head offices in Modena (MO), Italy, Viale Virgilio 58

PHONE +39 059.84.83.80 FAX + 39 059.84.87.90

VAT Number and Tax Code 02320040369

C.C.I.A.A. (Chamber of Commerce) registration Modena REA (economic and administrative index) 281649

INAIL (National Institute for Industrial Accident Insurance) registration no. 004513160/63 clerk no. 10853110 technical clerk no. 10853109

INPS (National Institute of Social Insurance) no. 5006198146

Employer: Paolo Fantuzzi

Health and Safety Manager: Roberta Bini Appointed Doctor: Alessandra Mussi Safety Representative: Silvia Pozzi

Activity carried out by the company: trade fair activity

b) Trade Fair Organiser

Depending on the type of event, the Organiser may be:

- 1. ModenaFiere srl
- 2. other Companies/Entities that promote, organise and manage the event in the area of the "ModenaFiere" Exhibition Centre.

c) Exhibitor Companies:

Companies/Entities that acquire, directly by the Organiser, an exhibition space in the Exhibition Centre.

d) Fitting Companies:

Companies hired directly by the Exhibitor, Organiser or, in case of subcontracting, a Fitter for the set-up and dismantling of the available exhibition space.

d) Suppliers to ModenaFiere srl and/or the Organiser.

Hereinafter the "Contracting Party" will refer to any company (Exhibitor, Fitter, Supplier, Organiser, etc.) who assigns to other parties "Contractors", work/supplies and installation/services within the "ModenaFiere" Exhibition Centre.

If the "Contracting Party" carries out any activities or work with its own employed personnel, then it will also be a "Contractor".

2. CONTRACTS AND SUB-CONTRACTS

With regard to all supply contracts, sub-contracts and work contracts, the Contracting Parties must comply with the provisions of Article 26 of Italian Legislative Decree 81/2008 as amended.

Contracts and sub-contracts must be formalised in writing so that sub-contractors will assume all of the obligations provided for the contractor and those stated in this document, in "Technical Regulations and Conditions for Participation in the Exhibition" and in "Safety Regulations of the Exhibition Centre".

As required by law, the Contracting Party must check the technical and professional qualifications of all contracting and sub-contracting companies.

Please see the Memorandum for Exhibitors attached to this document.

3. INFORMATION PROVIDED BY THE ORGANISER ON THE SPECIFIC RISKS PRESENT IN THE EXHIBITION CENTRE AND ON THE PREVENTION AND **EMERGENCY MEASURES**

a) Organisation ModenaFiere S.r.l.:

Contacts for the activities to be carried out in the premises managed by ModenaFiere srl:

- Secretariat PHONE +39 059.84.83.80 FAX +39 059.84.87.90
- Technical Department, Raffaele Nannetti mobile +39 335 349174 and Ferruccio Mirandola mobile +39 345 7551831
- Customer Service Department +39 338.68.34.546

b) Areas where the work is to be performed and exhibition calendar:

The floor plan of the exhibition centre is annexed.

c) Access to the areas where work is to be performed:

Unless otherwise indicated by the Organiser, the personnel of the Exhibiting/Fitting Companies must enter the Exhibition Centre from the driveway in Viale Virgilio and present their identification badges as required by article 26, subsection 8 of Italian Leg. Decree 81/08 as amended.

On entering the Exhibition Centre, the Exhibitor and Fitting Companies undertake to observe the contents of "Technical Regulations and Conditions for Participation in the Exhibition" and in "Safety Regulations of the Exhibition Centre".

The admission times and procedures are indicated in the above-mentioned Regulations.

The attached floor plans indicate:

- site plan of the exhibition centre and internal roads;
- floor plan indicating escape routes, fire-fighting equipment and first aid post.
- d) Plants, Machinery and Equipment present in the area subject to work and special protection measures/systems to be adopted:

Work on live electrical systems



ALL ELECTRICAL SYSTEMS ON THE PREMISES OF "MODENAFIERE" EXHIBITION CENTRE MUST BE ASSUMED TO BE LIVE, EVEN IN CASE OF TEMPORARY POWER FAILURES.

The halls are equipped with electrical panels to power the equipment of Contracting Parties and their Contractors (exhibitors, fitters, etc.) and with panels to supply electrical energy to the stand. The methods of connection of the stands to the mains are listed in the Safety Regulations of the Exhibition Centre.

In case of malfunction of service sockets or of electrical systems in general, contact the ModenaFiere srl Technical Department immediately.

It is strictly forbidden to work on the electrical service systems or to personally connect up the stand electrical system.



A PHOTOVOLTAIC SYSTEM IS INSTALLED ON THE CAR PARK COVERING AND ROOFING. IT IS FORBIDDEN TO THROW WATER ON THE PANELS AS THEY ARE ALWAYS LIVE IN DAYTIME.

Special measures/protection systems to be adopted:

System/Machine/ Equipment:	Owner:	User:	Type of use:	Information/Special measures/protection systems to be adopted:		
CARS, LORRIES, ARTICULATED LORRIES, APE CAR.	ModenaFiere srl Organiser Exhibitors Fitters Suppliers	ModenaFiere srl Organiser Exhibitors Fitters Suppliers	□ Exclusive ☑ Mixed	High-visibility clothing in external areas; Operator must be helped by a coworker on foot for critical manoeuvres and manoeuvres with poor visibility.		
LIFT TRUCKS, SMALL TRACTORS	ModenaFiere srl Organiser Fitters Suppliers	ModenaFiere srl Organiser Fitters Suppliers	□ Exclusive ☑ Mixed	Observe road markings and signs; Maximum speed inside the exhibiti centre: 15 Km/h.		
LORRIES - CRANES	Exhibitors Fitters Suppliers	Organiser Exhibitors Fitters Suppliers	□ Exclusive ☑ Mixed	Periodic checks of ropes and chains, annual checks by Local Health Authority; High-visibility clothing in external areas; Helmet in areas where there is a danger of objects falling from above; Delimiting and marking of areas involved in lifting/handling with two-colour tape; Operator must be helped by a co-worker on foot for critical manoeuvres and manoeuvres with poor visibility.		
PLATFORMS AND LIFT BASKETS	Exhibitors Fitters Suppliers	Exhibitors Fitters Suppliers	☑ Exclusive ☐ Mixed	Periodic checks, annual checks by Local Health Authority; Helmet in areas where there is a danger of objects falling from above; It is forbidden to transport and hoist materials; Delimiting and marking of areas involved in lifting/handling with two-colour tape; Safety harnesses.		
PORTABLE ELECTRICAL TOOLS AND MANUAL TOOLS	Exhibitors Fitters Suppliers	Exhibitors Fitters Suppliers	■ Exclusive □ Mixed	PPE (Personal Protection Equipment) needed depending on tool used.		
LADDERS - ROLLING SCAFFOLDS	Exhibitors Fitters Suppliers	Exhibitors Fitters Suppliers	☑ Exclusive☐ Mixed	Helmet in areas where there is a danger of objects falling from above; Delimiting and marking of areas involved with two-colour tape; Provision of holders for portable tools.		
BICYCLES	Organiser Fitters Exhibitors	Organiser Fitters Exhibitors	■ Exclusive □ Mixed	Speed limits for vehicles in exhibition centre Walkways must be kept to.		
ELECTRICAL SYSTEMS MECHANICAL SYSTEMS	ModenaFiere srl	Firms carrying out the work	□ Exclusive ☑ Mixed	Do not tamper with equipment and systems; Do not modify the systems on your own initiative; Only qualified personnel are allowed to perform work on the systems; Comply with the regulations in force concerning safety at work; Do not throw water on the photovoltaic panels.		
LIFTS	ModenaFiere srl	ModenaFiere srl Organiser Exhibitors Fitters Suppliers	□ Exclusive ☑ Mixed	May not be used for handling materials; Emergency call procedures in lifts; Must not be used in case of fire.		

Note. The above list is not exhaustive. The equipment indicated is not owned by the Organiser, and it is therefore impossible to provide preliminarily a complete list of the equipment that will be present when work is performed. Before starting work, the contractor is required to carry out an inspection to determine the condition of the premises.

Contracting Parties and Contractors are strictly prohibited from borrowing any tools, machines, and/or systems from other suppliers or third parties.

In case of lease/authorisation to use or hiring of machinery and equipment without operator (Art. 72 of Italian Leg. Decree 81/2008 as amended), Contracting Parties and/or Contractors must verify that such equipment conforms to the safety requirements specified in Annex V of Legislative Decree 81/2008 as amended, and that they include all necessary documentation.

e) Personnel present in the work zone:

The following personnel are present in the Exhibition Centre during set-up and dismantling periods:

- Exhibitors:
- Fitters hired directly by Exhibitor and subcontractors (if any);
- Employees of ModenaFiere srl and of the Organiser;
- Suppliers to ModenaFiere srl and the Organiser.

f) List of accident prevention devices and PPE.

During the pre and post fair period, all personnel working in the exhibition centre must be equipped with the following PPE – **Personal Protection Equipment**:

■ Safety shoes (to be worn at all times inside the exhibition centre)	☐ Goggles/Visors
☐ Protective gloves	■ Safety helmet*
■ Respiratory protective equipment*	■ Hearing protection*
■ Fall arresting devices ^	$\ensuremath{\boxtimes}$ What is necessary in relation to the specific risks of the contractor
■ High-visibility clothing °	

The individual employers are to decide the equipment and PPE according to the risks associated with specific jobs.

g) First aid and emergency management:

The Contractor must have personnel that are specifically trained to provide First Aid, fight fires, and manage emergencies.

In case of technical and health emergencies, adopt the measures described in the emergency procedure attached.

Accidents must always be reported to the ModenaFiere Technical Department +39 335.349174 and +39 345 7551831 or to the Customer Service Department +39 338.68.34.546.

h) Connection to the following utilities:

The methods and connection points to utilities provided at ModenaFiere's expense and/or necessary for work must be arranged with the ModenaFiere srl Technical Department or with the firms specifically appointed by ModenaFiere.

i) **General rules of conduct:**

- Do not carry out any work (repairs or replacements) on live parts. Use only portable electrical tools with double insulation. Only fully functional electrical equipment must be used
- Do not leave electrical cables/extension cords on the floor, in areas of transit/walkways, or where they are exposed to crushing. Make sure that electrical cables are adequately protected against mechanical damage. Before starting to work and at the end of the day, check the efficiency of the electrical systems by visually inspecting the state of cables and connections.
- All openings onto empty space must be protected with appropriate guardrails. (Annex XVIII 2.1.5 Italian Leg. Decree. 81/2008 as amended: the guardrail referred to in Art. 126 of section IV consists of one or more elements parallel to the floor, the upper margin of which is located not less than one metre from the walking area, and a toeboard not less than 20 cm high, placed edge-wise and resting on the walking area).
- Make sure that passageways are not obstructed by scrap materials.
- Follow the safety instructions on the safety cards for the products handled.
- Use PPE suitable for the specific risks associated with the equipment, products and activities.

^{*} Use is optional depending on surrounding conditions.

Use is mandatory in external areas adjacent to traffic zones during work.

[^] Use is mandatory on platforms or baskets or work at heights in general if the operator is not protected by temporary works, and in case of provision of antifall system (PPE III class with compulsory training).

- Enter work areas via specified passageways only; in particular, do not use unsafe routes.
- Keep the workplace tidy; remove all obstacles that may cause risk of falling, slipping and injury from walkways.
- 9. Avoid dangerous situations for yourself and others, such as dangerous acrobatics, clothing that may become entangled with moving parts, handling bulky loads with methods that may harm third parties, using machines in improper ways.
- 10. Prevent access by unauthorised personnel.
- 11. Observe the "Technical Regulations and Conditions for Participation in the Exhibition" (LINK TO REGULATIONS) and "Safety Regulations of the Exhibition Centre" (LINK TO SAFETY).
- 12. Do not drink alcoholic beverages or take psychotropic substances.
- 13. The dispersion of dust generated when cutting materials (wood, ceramics, metals) must be reduced by using appropriate extraction systems or by performing the work outside the halls.
- 14. Do not use ladders if more suitable fixed and/or rolling scaffolds are available.
- 15. Each Contractor must dispose of waste in accordance with current law.

In general, the Exhibitor and/or the Contracting Party must: j)

- Have formalised in writing their supply contracts, sub-contracts, and work contracts with their suppliers according to the criteria provided by current law;
- Have checked the technical and professional qualifications for contracted and sub-contracted activities in accordance with art. 26 subsection 1, letter a) of Italian Leg. Decree 81/2008 as amended:
- If more than one company is involved in the stand set-up work, prepare the DUVRI (Interference Risk Assessment Document) regarding the activities that are to be conducted inside the relevant areas (stands) in order to coordinate contractors and subcontractors; in view of the type of activity, the DUVRI, which also refer to the general DUVRI of the exhibition, must contain a schedule of works.
- Have informed contracting firms of the risks present in the Exhibition Centre.

k) In general, Fitters, Suppliers and Contractors must:

- comply with insurance and social security regulations;
- possess the technical and professional requirements for the contracted activities;
- have checked the technical and professional qualifications of subcontractors and/or selfemployed workers in compliance with art. 26 subsection 1, letter a) of Italian Leg. Decree 81/08 as amended;
- have prepared the risk assessment document (or self-certification) pursuant to Italian Leg. Decree 81/2008 as amended;
- when performing contracted work, comply with the general safety measures referred to in Art. 15 of Italian Leg. Decree 81/2008 as amended;
- have designated the workers responsible for implementing fire-prevention and fire-fighting measures;
- have informed and trained employees with regard to the specific risks they may be exposed to in connection with their working activities (articles 36 and 37 of Italian Leg. Decree 81/2008 as amended), the use of PPE, and the specific risks associated with the contract in question by writing Safety Plans and/or procedures and schemes for setting up the stand;
- make and keep within a copy of the documentation available with reference to the above in case of controls by the Authorities;
- subject the employees to health surveillance as required by law.

6. SAFETY COSTS

Based on the instructions contained in this document, the Contracting Party must indicate the safety costs of contracted activities in supply contracts, sub-contracts, and work contracts.

The total amount of the works and/or services subject to contract/sub-contract/supply contract, including the costs of safety, must be specified in the contract, which must also indicate the cost of safety with regard to executing works with adoption of all appropriate means to prevent and protect against workplace risks generated by interference.

The assessed costs must include, among other things, the following items:

- specific information on workers per activity in the exhibition centre;
- PPE for interfering activities;
- barricades and barriers to indicate work in progress;
- specific signs.

7. ACTIVITIES CONDUCTED DURING THE EXHIBITION IN THE PRESENCE OF THE PUBLIC.

If activities are conducted in the presence of the public, in addition to compliance with the "Technical Regulations and Conditions for Participation in the Exhibition", "Safety Regulations of the Exhibition Centre" and the instructions given in the previous sections, the firm carrying out the work must cordon off the areas and contact the ModenaFiere srl Technical Department if access to the areas is to be restricted for safety reasons.

In case of work inside the stands, the firm carrying out the work **must implement the** following PROCEDURE before entering a stand:

- 1. Notify the stand personnel and ask whether work can commence;
- 2. Co-ordinate work with stand personnel to identify work areas;
- 3. Refrain from performing any work or procedures requested by the stand operator that are contrary to the "Technical Regulations and Conditions for Participation in the Exhibition", to the "Safety Regulations of the Exhibition Centre" or to the current law on work safety and industrial hygiene.

_					
n	\mathbf{N}	DI/ I	NITER) F F D	ENCE
_	WWUJ	KK I	141 1 6 6	KFFK	FINU.F

Is there any work interference?:

\boxtimes	Yes
-------------	-----

	No
--	----

The Contracting Parties and Contractors referred to in this document may work, both during set-up and disassembly operations and during the exhibition, in the stands and spaces managed by **Exhibitors**. There may be various types of interference, including:

- 1. overlapping of work activities in the same stand, with other firms, with fitters, or with the exhibitor's activity;
- 2. interference with suppliers to ModenaFiere srl and ModenaFiere srl personnel responsible for supervising the fitters and exhibitors;
- 3. overlapping with work performed in adjacent stands;
- 4. interference with vehicular traffic in the hall and on roads.

The measures to be taken must necessarily be determined in situ on the basis of information received from ModenaFiere srl and current legislation on health and safety at work, and must be co-ordinated with the Exhibitor and with other workers present, taking special care to:

- separate the interfering activities in time or spatially by dividing the stand into separate areas;
- not to obstruct the longitudinal pathways and in particular the escape routes shown in the attached floor plan;
- if it should be necessary to work with ladders and rolling scaffolds in shared paths that can also be used by trucks, the area involved must be cordoned off and marked.
- <u>ModenaFiere's Supplier will not switch on power to the stand if a request has not been made to the relevant office on delivery of the declaration of conformity prepared pursuant to the Italian Ministerial Decree no. 37/08 and if stand personnel are not present for arranging the time of connection.</u>

Measures adopted to eliminate observed work interference (non-exhaustive measures, see also "Technical Regulations and Conditions for Participation in the Exhibition" and "Safety Regulations of the Exhibition Centre")

Please refer to the following table to classify R risks:

8 ≤ R ≤ 16 Very	4 ≤ R < 8 High	2 ≤ R ≤ 3 Medium Injury	R = 1 Low
HighAccident that may result in death or total	Injury that may result in permanent partial disability.	resulting in reversible disability.	Minor injury curable within a few days.
and/or permanent disability.	permanent partial disability.	disability.	a lew days.

wo	Areas where work is performed Risks of interference		R		urity measures rmation notes	•	any responsible for ring the safety ures
	varde	1 Collisions between lift	trucks	4	1.1 Inform/train operators		



as where k is formed	Risks of interference	R		•	n notes p	ompany responsible for reparing the safety easures
car parks halls	motor vehicles, small tractor other vehicles present	in the		1.2	Operator must be helped by a co-worker on foot for critical manoeuv and manoeuvres with poor visibility	res
gallery	exhibition centre and vehi			1.3	Use mainly the routes shown on the attached floor plan (yellow lanes).
J	exhibitors, fitters, contractors and suppliers.	other		1.4	Maximum speed: 5 km/h.	
	33333333333			1.5	During set-up and dismantling periods, speed must be further redu according to actual traffic and crowding conditions.	ced
	2. Tripping and falling			2.1	It is strictly forbidden to deposit materials on walkways.	
	obstacles on floor, such as materials and waste materi			2.2	Inform/train operators	Contractors
	by fitters on walkways duri and post fair activities.		3	2.3	Pay special attention to the plastic sheets that are left or placed protect the carpet during set-up.	to
	and poor ian assistance.			2.4	Contact the reference person for ModenaFiere srl to ask for material be removed.	Contractors/ModenaFig
	Noise 4. Operators hit by lift true motor vehicles or small tractors			3.1	The Contractor must adopt all technical measures to reduce emission of noise and vibrations deriving from work performed by employees. If noise and vibrations are generated by others working the vicinity, the contractor must provide his personnel with PPE.	its
			2	3.2	The values measured by ModenaFiere srl during the exhibition activities are below the legal limits. During set-up and dismantling per operations may be carried out that involve exposure to noise. Contractor must check any specific exposure related to surround activities.	ods The
				4.1	Lift truck drivers must have received special theoretical and practraining from the contractor.	ical
				4.2	Workers in yards and in areas with poor visibility must wear h visibility clothing.	gh-
			6	4.3	Use the walkways. Pay attention to vehicles in circulation when exithe halls.	Contractors
				4.4	Maximum speed: 5 km/h.	
				4.5	During set-up and dismantling periods, speed must be further redu according to actual traffic and crowding conditions.	ced
				4.6	Inform/train operators	
	5. Cuts caused by mater		_	5.1	Safety shoes must be worn in all areas.	
	waste left on floor (nails, etc.)	glass,	4	5.2	Dispose of waste materials.	Contractors
	existing wells and/or hatch			6.1	The area involved must be marked and cordoned off.	Firm performing spe work
	access to trenches left op	oen for	3	6.2	Close the well at the end of work.	Contractors
	maintenance.			6.3	Inform/train operators.	Contractors
yards car parks	7. Personnel falling from rescaffolds, ladders or fixed	olling		7.1	The work area must be marked and cordoned off.	Firm performing spe work
halls	scaffolding due to collision w	vith	6	7.2	Inform/train workers.	Contractors
gallery	trucks, pallet trucks and/or			7.3	Maximum speed: 5 km/h.	Contractors



reas where Risks of interference ork is erformed		R	Information notes pre		ompany responsible for reparing the safety reasures	
	machines.		7.4 The contractor must organize work by limiting/eliminating ladders and using appropriate equipment.	the use	of	
yards car parks halls gallery	8. Various interference due to the presence of the public)	8.1 Make sure that the work area is always delimited by barriers and that regulation signage is provided.8.2 The lift trucks may not enter the halls during the exhibition.	and tape	Contractors	
9. Presence of exhaust gas from non-electric vehicles. halls gallery		om	9.1 It is forbidden to enter the halls with vehicles that do not have traction or that are not equipped with catalytic muffler and ap- pipes to eliminate exhaust gas. Inform the contact per ModenaFiere srl.	oropriate		
yards			9.2 Inform/train operators.9.3 Use of a mask is recommended when working outdoors on d heavy traffic.	ays with	Contractors	
halls	10. Inhalation of dust	:	10.1 It is forbidden to cut materials in the halls without appropri extraction devices. Carry out work outdoors.	ate dust	Contractors	
gallery	11. Microclimate		11.1 During set-up and dismantling of stands the heating syster working.	n is not	//	
yards	12. Objects falling from above		12.1 Areas involved in handling operations and work at height marked and cordoned off.12.2 Do not place any materials (even temporarily) on structures or owned by ModenaFiere srl.	systems		
car parks halls gallery			12.3 The Contractor's operators must wear a safety helmet when we the halls during the pre and post fair period.12.4 It is strictly forbidden to hoist materials on a liftable platform.	orking in	Contractors	
			12.5 Materials may not be deposited on intermediate floors, etc. wit prior consent of ModenaFiere srl.	hout the		
yards car parks halls	13. Collision, crushing due to material falling from lift trucks movement and loading/unloadi		 12.6 Inform/train operators. 13.1 Inform/train truck operators. 13.2 High-visibility clothing must be worn in external areas. 13.3 Operator must be helped by a co-worker on foot for critical man and manoeuvres with poor visibility. 13.4 The weight and dimensions of the handled load must be compated. 		Contractors	
halls gallery offices/meeting	14. Fire		the characteristics of the vehicle. 14.1 Flammable materials may not be deposited anywhere in the ecentre. Only the quantities of products needed for daily work stored.	xhibition	Contractors	
rooms			14.2 Batteries may be recharged only outside the halls.14.3 Train/inform operators.			



reas where ork is erformed	Risks of interference	R		formation notes	Company responsible for preparing the safety measures
				14.4 Activity requiring a Fire Prevention Certificate. Presence of teams trained personnel. Each Contractor must still be able to cope with an emergencies with its own staff. The fire extinguisher required by the "Technical Regulations and Conditions for Participation in the Exhibition must be placed in the stand on the first day of set-up and stay the until the end of all dismantling work.	ny ne n"
				14.5 Smoking is forbidden inside the halls, even during the fitting ar dismantling work.	nd
halls gallery	15. Explosion		1	14.6 Naked flames must not be used inside the exhibition centre.15.1 The batteries of electric lift trucks must not be recharged inside the halls.	ne Contractors
Halls External areas	16. Projection of material		2	16.1 The area involved must be marked and cordoned off.	Contractors
halls gallery	17. Exposure to chemicals		2	 17.1 Train/inform operators. 17.2 Presence of safety sheets in the areas where work will be performed. 17.3 It is strictly forbidden to deposit materials. 17.4 Inform third parties of the risks associated. 17.5 The Contractor is obliged to adopt all technical measures for reducing the formation and diffusion of dust, fumes, vapours and odours deriving 	
	18. Persons falling from a heigh	nt		from the operations performed and which are toxic, flammable are irrespirable or in any case unpleasant or harmful. 18.1 When working on stands and during set-up/dismantling, Contractor	s'
				personnel may not use the stand structures as work surfaces, support etc. 18.2 It is strictly forbidden to transport and lift people on lift trucks. 18.3 Work positions at height on intermediate floors or on stand structure during set-up must be equipped with temporary measures to prote against falling or certified antifall systems. Operators must be adequately trained in the use of safety harnesses (class III PPE).	es ct
yards car parks halls gallery			6	 18.4 Operators may not access any work area by leaving an aerial buck truck. 18.5 Close attention must be drawn to the methods of work at height (dang of falling from a height). It is specifically required to provide ear operator with lifelines and/or safety hooks on which safety belts must be fastened. The presence of such fixed safety devices (lifelines, fixed hooks) and the use by the operator of the specific personal protective equipment (PPE) designed to eliminate the risk of falling from a height are preliminary conditions to start any maintenance work. It is forbidden to perform any work if these safety conditions are not met. 	Contractors de d
				18.6 When using a platform, operators must be harnessed and secured supports. Areas below must be marked and cordoned off. Operato must be adequately trained in and informed about the use of class I PPE. Platforms must have the required documentation and must be checked annually by competent Authorities.	rs II



wo	eas where ork is rformed	Ri	sks of interference	R		ecurity measures nformation notes	pr	empany responsible for eparing the safety easures
			19. Electric shock			19.1 An appropriate "work in progress" sign must be installed when w carried out on the system.	ork is	Firm performing specific work
			NOTE: SYSTEMS MUST E ASSUMED LIVE!!	<u>3E</u>		19.2 Personnel acting on behalf of ModenaFiere srl may connect the stathe mains only after the fitting firm has delivered the declaration conformity.		ModenaFiere srl/ Contractors/Supplier to ModenaFiere srl
					19.3 Inform/train operators.			
						19.4 Comply with the regulations in force concerning safety at work;		
	Entire exhibit	tion			8	19.5 Do not modify the systems on your own initiative; only qu personnel are allowed to perform work on the systems;	alified	
						19.6 Electrical cables located in lift truck and vehicle lanes must be prote		
						19.7 Do not tamper with equipment and systems; it is forbidden to perwork on electrical panels and/or systems owned by ModenaFiere sr		Contractors
					19.8 Electrical cables and extension cords must be in good condition, without abrasions or cuts.			
					19.9 It is mandatory to use electrical connections with protection adequate for the work environment (presence of dust and water).	level		
						19.10 Do not throw water on the photovoltaic panels.		
yards halls		escape	eccupation of traffic and routes, obstruction of ency doors (due to work)			walkways and traffic lanes must be indicated with signs.	Firm specif Contr	performing fic activity/ actors
gallery				4	20.2	Train/inform operators.		
offices						Do not obstruct emergency traffic lanes, escape routes or emergency doors by parking work vehicles and/or depositing materials.	Contr	actors
		21. Va	arious interference			When lifting and positioning machinery and/or equipment, the contractor should preferably occupy its own stand area. If the stand area is not sufficient for the size of the machine, the whole area involved must be cordoned off and work must be coordinated with exhibitors in adjacent areas.	Contra	actors
EXTER! EXHIBI	NAL TION AREAS	REAS		4		The machinery on show may not be operated, not even for demonstration purposes. The Technical Department of ModenaFiere may grant written permissions provided this does not cause any nuisance or risk or danger to third parties. In any case, the exhibitor is obliged to equip machinery with all the devices necessary to prevent accidents, noise, unpleasant odours and emissions of gases and liquids. It is also forbidden for Exhibitors to let third party operators or the public access work positions at height (> 2m).	Exhibi	tors
						If the exhibitor performs work or fitting operations such as to fall within the field of application of Title IV, Italian Leg. Decree 81/2008 as amended (formerly Leg. Decree 494/96) he must meet the requirements and pay the relevant costs of the above-mentioned decree. He must in any case notify ModenaFiere srl.		



	Areas where work is performed	Risks of interference	F	₹	Security measures Information notes	Company responsible for preparing the safety measures
				21	.4 It is generally forbidden to handle materials during exhibitions, even for demonstration purposes. The competent office of ModenaFiere srl may be asked for a written permission and in any case materials must be handled in the stand area only. The exhibitor must cordon off the area involved.	
s)	notovoltaic ystem Visitor arking and edestrian walkway	Fire - Electric shock	4	21	 .5 A photovoltaic system is installed on the canopies in the parking area and on the covering of the pedestrian walkway. The panels are always live in the daytime. It is forbidden to use water. .6 To work on these systems proceed as follows: perform routine and scheduled maintenance work preferably on the days and in the times when exhibitions and/or set-up/dismantling work do not take place; mark and cordon off the work areas; set the system in a safety status; find an alternate route for third parties. 7 Close attention must be drawn to the methods of work at height (danger of falling from a height). It is specifically required to provide each operator with lifelines and/or safety hooks on which safety belts must be fastened. The presence of such fixed safety devices (lifelines, fixed hooks) and the use by the operator of the specific personal protective equipment (PPE) designed to eliminate the risk of falling from a height are preliminary conditions to start any maintenance work. It is forbidden to perform any work if these safety conditions are not met. 	ModenaFiere srl/Suppliers

NOTE. Contractors must eliminate risks due to possible interference with set-up work performed by other firms and coordinate their activities as necessary. Each firm must work with its own tools and equipment: it is strictly forbidden to use any tools or equipment borrowed from other fitters/exhibitors.



9. ATTACHMENTS

Floor plan of the exhibition centre

Floor plan indicating escape routes, fire-fighting equipment and first aid post

Technical Regulations and Conditions for Participation in the Exhibition

Safety Regulations of the Exhibition Centre

Emergency Procedure

Exhibitors Memorandum

Modena, 14 October 2013

